



REPORT NUMBER: 101113787COQ-004 ORIGINAL ISSUE DATE: July 3, 2013

### **EVALUATION CENTER**

INTERTEK TESTING SERVICES NA LTD. 1500 BRIGANTINE DRIVE COQUITLAM, BC V3K 7C1

### **RENDERED TO**

CEMENT BOARD FABRICATORS, INC. 2148 S. 41<sup>ST</sup> STREET LOUISVILLE, KY 40211

PRODUCT EVALUATED: Silbonit<sup>™</sup> Fiber-Cement Flat Sheets EVALUATION PROPERTY: Transverse Load Testing

Report of Silbonit<sup>™</sup> Fiber-Cement Flat Sheets tested in accordance with ASTM E330-02(2010), Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to copy or distribute this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

# 1 Table of Contents

1	Tab	ole Of Contents	2
2	Intro	oduction	3
3	Tes	st Samples	3
	3.1.	Sample Selection	3
	3.2.	Sample And Assembly Description	3
4	Tes	sting And Evaluation Methods	3
	4.1.	Conditioning	3
	4.2.	Transverse Load	3
5	Tes	sting And Evaluation Results	5
	5.1.	Results And Observations	5
6	Con	nclusion	5
Α	ppendix	x A Test Data5	Pages

### 2 Introduction

Intertek Testing Services NA Ltd. (Intertek) has conducted Transverse Load Testing for Cement Board Fabricators, Inc. on a fiber-cement panel product. The testing was carried out in accordance with ASTM E330-02(2010), Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference. This evaluation was completed during the month of April 2013.

### 3 Test Samples

### 3.1. SAMPLE SELECTION

The client submitted the fiber-cement panels to the Evaluation Center on April 8, 2013 (Coquitlam ID# VAN1304081354-001). Samples were not independently selected for testing.

### 3.2. SAMPLE AND ASSEMBLY DESCRIPTION

The product was identified as the Silbonit<sup>TM</sup> Fiber-Cement Flat Sheets, a fiber-reinforced panel product measuring nominal 4 ft.  $\times$  8 ft.  $\times$  5/16 in. thick and weighing 3 lbs/ft<sup>2</sup>.

## 4 Testing and Evaluation Methods

### 4.1. CONDITIONING

Unless otherwise stated, the sample materials were maintained in standard laboratory conditions for a minimum of 7 days at a temperature of  $73 \pm 4 \%$  (23  $\pm 2 \%$ ) and relative humidity of  $50 \pm 5\%$ .

### 4.2. TRANSVERSE LOAD

Transverse load testing was conducted in accordance with ASTM E330-02(2010). Test frames, measuring 4 ft. x 8 ft., were constructed from SPF #2+BTR, nominal 2 in. x 4 in. lumber, spaced 24 in. on center. Frames were fastened together using 3-1/2 in. deck screws.

A total of four (4) assemblies were constructed for transverse load - three (3) assemblies for the negative wind load direction and one (1) assembly for the positive wind load direction. Plywood furring strips, measuring 1-1/2 in. x 3/4 in., were installed to the vertical stud locations. Client-supplied EPDM rubber strips were then fastened to the furring strips. The Silbonit<sup>TM</sup> panels were installed vertically over the EPDM rubber strips using the supplied stainless steel 1-1/2 in. long screws spaced every 16 in. o/c along the studs (16 screws total per test assembly). Installation of the test panels were in accordance with the manufacturer's installation instructions.

Testing was conducted using the chamber method for uniformly distributed loading. Each test frame was secured in a horizontal uniformly distributed load testing apparatus. The air within the test chamber was evacuated using a vacuum pump, inducing a uniformly distributed load to the sample. A polyethylene film was used to prevent air leakage through the panel. In order to ensure the maximum load was transferred to the specimen and that the polyethylene film did not prevent movement or failure of the specimen, the polyethylene film was applied loosely with extra folds of material at each corner and at all offsets and recesses. For negative load tests



the polyethylene film was placed on the inner face of the panel during construction of the assembly. The test was carried out without restriction of any relative movement between the panel material and any part of the test assembly or test apparatus.

Deflection readings were recorded for each test to establish deformation and set characteristics. For all test configurations, five (5) gauges were set on the test specimen. Gauge locations can be found on the data sheets in Appendix A. All deflection measurements were made independent of the test specimens.

The load was increased to prescribed load increments where the deformation was recorded after holding for 10 seconds each. The load was then released where the deformation was recorded after a period of not less than 1 minute or more than 5 minutes. This sequence of deformation measurements was repeated a minimum of five times until a final ultimate load was attained. A visual examination of the specimens was made after the tests to determine the failure mode.



## 5 Testing and Evaluation Results

### 5.1. RESULTS AND OBSERVATIONS

The test results are shown in Table 1 below. A full set of test data for the Silbonit<sup>™</sup> Fiber-Cement Flat Sheets product is included in Appendix A.

Table 1. Test Results							
Panel	Framing	Stud Spacing	Direction	Ultimate Load (psf)	Average Ultimate Load (psf)		
	Wood 2" x 4" SPF #2+BTR	24" O/C		156.1			
Silbonit <sup>™</sup> Fiber-Cement			Negative Wind Load	156.1	156.1		
Flat Sheets				156.1			
			Positive Wind Load	150.9	N/A		

### 6 Conclusion

The Cement Board Fabricators, Inc. Silbonit<sup>™</sup> Fiber-Cement Flat Sheets product identified and evaluated in this report has been tested in accordance with ASTM E330-02(2010), *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference.* The product test results are presented in Section 5 of this report.

INTERTEK TESTING SERVICES NA LTD.

Reported by:


Chris Chang, P.Eng.

Engineer, Building Products

Reviewed by:

Ríccardo DeSantis

Manager, Building Products







Test Data Package Page 1 of 5

Company	Cement Board Fabricators, Inc.	Technician(s)	Kevin Penner
Project No.	G101113787	Reviewer	Riccardo DeSantis K.D.
Models	Silbonit™ Fiber-Cement Flat Sheets	Start/End Date	April 25, 2013
Product Name	Same as above	Sample ID	VAN1304081354-001
Standard	ASTM E330-02(2010), Standard Test Method for Structural Pe Walls by Uniform Static Air Pressure Difference	rformance of Ex	tterior Windows, Doors, Skylights and Curtain

### **Test Data Package**

### **Table of Contents**

Sheet	Page
Table of Contents (This Sheet)	1
Transverse Load Test #1 - Negative Wind Load	2
Transverse Load Test #2 - Negative Wind Load	3
Transverse Load Test #3 - Negative Wind Load	4
Transverse Load Test #4 - Positive Wind Load	5



Test: Transverse Load - Negative Wind Load Client:

Cement Board Fabricators, Inc.

25-Apr-13 Date:

Product: Silbonit Fiber-Cement Flat Sheets

ASTM E330-02(2010), Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Test Method(s):

Walls by Uniform Static Air Pressure Difference

Installation: Configuration: Wood

Nominal 2x4 SPF #2&BTR lumber studs spaced 24 in. o/c, fastened with 3-1/2 in. deck screws Framing:

TEST #1

Project#: G101113787

Riccardo DeSantis

Technician(s): Kevin Penner

Reviewer:

Fastener: 1-1/2 in. long Stainless steel pan head screw (supplied by client)

Fastener Spacing: 16 in. o/c along studs (21 screws total)

Equipment:

36" Dwyer Manometer (Intertek ID# 2056)

1 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60021, cal due November 2013) 2 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60175, cal due November 2013) 3 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02699, cal due November 2013) 4 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02768, cal due November 2013) 5 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60020, cal due November 2013)

Vaisala Temperature and Relative Humidity Indicator (Intertek ID# 9-0176, cal due June 2013)


Time/Temp/RH: 1:40PM / 20.9℃ / 38.5%


Test Assembly					
Width (ft)	Length (ft)				
8.0	4.0				

Load (in WC)	Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)
0.0	0.0	immed.	0.000	0.000	0.000	0.000	0.000
15.0	78.0	10 sec.	N/A	N/A	N/A	N/A	N/A
0.0	0.0	1-5mins	Zero Deflection Gauges				
5.0	26.0	10 sec.	0.030	0.131	0.122	0.016	0.027
0.0	0.0	1-5mins	0.000	-0.001	-0.001	0.000	-0.001
10.0	52.0	10 sec.	0.049	0.270	0.251	0.025	0.041
0.0	0.0	1-5mins	0.001	0.001	0.001	0.001	0.000
15.0	78.0	10 sec.	0.064	0.398	0.376	0.032	0.050
0.0	0.0	1-5mins	0.001	0.006	0.005	0.002	0.001
20.0	104.0	10 sec.	0.078	0.533	0.511	0.038	0.059
0.0	0.0	1-5mins	0.002	0.014	0.014	0.003	0.004
25.0	130.1	10 sec.	0.090	0.663	0.648	0.041	0.066
0.0	0.0	1-5mins	0.003	0.023	0.026	0.004	0.008

#### Mode of Failure









Test: Transverse Load - Negative Wind Load Client:

Cement Board Fabricators, Inc.

25-Apr-13 Date:

Product: Silbonit Fiber-Cement Flat Sheets

ASTM E330-02(2010), Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Test Method(s):

Walls by Uniform Static Air Pressure Difference

Installation: Configuration: Wood

Nominal 2x4 SPF #2&BTR lumber studs spaced 24 in. o/c, fastened with 3-1/2 in. deck screws Framing:

TEST #2

Project#: G101113787

Riccardo DeSantis

Technician(s): Kevin Penner

Reviewer:

Fastener: 1-1/2 in. long Stainless steel pan head screw (supplied by client)

Fastener Spacing: 16 in. o/c along studs (21 screws total)

Equipment:

36" Dwyer Manometer (Intertek ID# 2056)

1 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60021, cal due November 2013) 2 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60175, cal due November 2013) 3 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02699, cal due November 2013) 4 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02768, cal due November 2013) 5 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60020, cal due November 2013)

Vaisala Temperature and Relative Humidity Indicator (Intertek ID# 9-0176, cal due June 2013)


Time/Temp/RH: 1:40PM / 20.9℃ / 38.5%


Test Assembly					
Width (ft)	Length (ft)				
8.0	4.0				

Load (in WC)	Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)
0.0	0.0	immed.	0.000	0.000	0.000	0.000	0.000
15.0	78.0	10 sec.	N/A	N/A	N/A	N/A	N/A
0.0	0.0	1-5mins	Zero Deflection Gauges				
5.0	26.0	10 sec.	0.032	0.095	0.100	0.015	0.022
0.0	0.0	1-5mins	0.001	0.001	0.001	0.001	0.000
10.0	52.0	10 sec.	0.050	0.207	0.213	0.024	0.034
0.0	0.0	1-5mins	0.001	0.002	0.002	0.001	0.000
15.0	78.0	10 sec.	0.062	0.316	0.324	0.031	0.043
0.0	0.0	1-5mins	0.002	0.003	0.004	0.002	0.000
20.0	104.0	10 sec.	0.073	0.428	0.439	0.035	0.053
0.0	0.0	1-5mins	0.004	0.010	0.011	0.003	0.003
25.0	130.1	10 sec.	0.084	0.533	0.558	0.038	0.059
0.0	0.0	1-5mins	0.005	0.013	0.019	0.004	0.004

#### Mode of Failure









Test: Transverse Load - Negative Wind Load Client:

Cement Board Fabricators, Inc.

25-Apr-13 Date:

Product: Silbonit Fiber-Cement Flat Sheets

ASTM E330-02(2010), Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Test Method(s):

Walls by Uniform Static Air Pressure Difference

Installation: Configuration: Wood

Nominal 2x4 SPF #2&BTR lumber studs spaced 24 in. o/c, fastened with 3-1/2 in. deck screws Framing:

TEST#3

Project#: G101113787

Riccardo DeSantis

Technician(s): Kevin Penner

Reviewer:

Fastener: 1-1/2 in. long Stainless steel pan head screw (supplied by client)

Fastener Spacing: 16 in. o/c along studs (21 screws total)

Equipment:

36" Dwyer Manometer (Intertek ID# 2056)

1 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60021, cal due November 2013) 2 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60175, cal due November 2013) 3 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02699, cal due November 2013) 4 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02768, cal due November 2013) 5 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60020, cal due November 2013)

Vaisala Temperature and Relative Humidity Indicator (Intertek ID# 9-0176, cal due June 2013)


Time/Temp/RH: 1:40PM / 20.9℃ / 38.5%


Test Assembly					
Width (ft)	Length (ft)				
8.0	4.0				

Load (in WC)	Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)
0.0	0.0	immed.	0.000	0.000	0.000	0.000	0.000
15.0	78.0	10 sec.	N/A	N/A	N/A	N/A	N/A
0.0	0.0	1-5mins	Zero Deflection Gauges				
5.0	26.0	10 sec.	0.028	0.137	0.131	0.025	0.030
0.0	0.0	1-5mins	0.001	0.001	0.001	0.001	0.001
10.0	52.0	10 sec.	0.043	0.292	0.275	0.039	0.051
0.0	0.0	1-5mins	0.002	0.003	0.003	0.003	0.002
15.0	78.0	10 sec.	0.053	0.431	0.407	0.048	0.064
0.0	0.0	1-5mins	0.002	0.007	0.008	0.004	0.003
20.0	104.0	10 sec.	0.065	0.578	0.548	0.060	0.075
0.0	0.0	1-5mins	0.006	0.019	0.021	0.008	0.006
25.0	130.1	10 sec.	0.076	0.713	0.678	0.067	0.083
0.0	0.0	1-5mins	0.010	0.028	0.033	0.012	0.008

#### Mode of Failure









Test: Transverse Load - Positive Wind Load TEST #4 Project#: G101113787

Client: Cement Board Fabricators, Inc.

Date: 25-Apr-13

Product: Silbonit Fiber-Cement Flat Sheets

Test Method(s): ASTM E330-02(2010), Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain

Walls by Uniform Static Air Pressure Difference

Installation: Configuration: Wood

Framing: Nominal 2x4 SPF #2&BTR lumber studs spaced 24 in. o/c, fastened with 3-1/2 in. deck screws

Fastener: 1-1/2 in. long Stainless steel pan head screw (supplied by client)

Fastener Spacing: 16 in. o/c along studs (21 screws total)

Equipment:

36" Dwyer Manometer (Intertek ID# 2056)

1 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60021, cal due November 2013)
2 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60175, cal due November 2013)
3 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02699, cal due November 2013)
4 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# 02768, cal due November 2013)
5 - 2 in. Mitutoyo Digital Deflection Gauge (Intertek ID# P60020, cal due November 2013)

Vaisala Temperature and Relative Humidity Indicator (Intertek ID# 9-0176, cal due June 2013)


Time/Temp/RH: 1:40PM / 20.9°C / 38.5%


Test Assembly					
Width (ft)	Length (ft)				
8.0	4.0				

Load (in WC)	Load (psf)	Time	Gauge 1 (in.)	Gauge 2 (in.)	Gauge 3 (in.)	Gauge 4 (in.)	Gauge 5 (in.)
0.0	0.0	immed.	0.000	0.000	0.000	0.000	0.000
15.0	78.0	10 sec.	N/A	N/A	N/A	N/A	N/A
0.0	0.0	1-5mins	Zero Deflection Gauges				
5.0	26.0	10 sec.	0.089	0.089	0.110	0.039	0.047
0.0	0.0	1-5mins	-0.002	-0.002	-0.001	0.000	0.000
10.0	52.0	10 sec.	0.182	0.192	0.234	0.086	0.095
0.0	0.0	1-5mins	0.001	0.000	0.000	0.000	0.000
15.0	78.0	10 sec.	0.241	0.290	0.350	0.113	0.142
0.0	0.0	1-5mins	0.001	0.002	0.002	0.000	0.002
20.0	104.0	10 sec.	0.330	0.396	0.491	0.131	0.199
0.0	0.0	1-5mins	0.008	0.003	0.043	0.010	0.051
25.0	130.1	10 sec.	0.425	0.475	0.692	0.145	0.452
0.0	0.0	1-5mins	0.012	0.013	0.052	0.013	0.055

### Mode of Failure







Technician(s): Kevin Penner

Reviewer:

Riccardo DeSantis